

## **GLENLAKE PUMP STATION DECOMMISSIONING**

### Outline:

1. Purpose of the Project
  - Investigating the feasibility of connecting a 12” water line between Big View Drive and Glen Lake Drive to provide service for Glenlake residents served by the old pump station & provide a redundant source of water for other Glenlake residents.
  - Install fire hydrants to enhance fire protection
2. What are included in the Project so far?
  - Installing:
    - 873 LF of 12-inch diameter DI water main
    - 140 LF of 8-inch diameter DI water main
    - 22 LF of 6-inch diameter DI water mains
    - 6 gate valves, 3 fire hydrants, and 2 air release valves.
    - Pressure reducing vault, a meter vault and pressure point station
  - Remove existing 8” asbestos cement pipe.
  - Demolition old pump station
  - Overlay in designated area prescribed in construction plan.  
(See attached exhibit)
3. Construction schedule:  
Approximately Fall 2018  
Duration: ~ 12 months
4. What will be affected during construction?
  - Lane closures (911 Driveway: will be opened during construction.)
  - Two new Fire Hydrants will be installed in Right of Way (ROW)
  - Affected areas due to shutout plan (see attached shut-out plan)
5. Question and comments
6. Contact information:
  - Austin Water sponsor: Bryan Barnett, P.E.  
512-972-0162  
Bryan.Barnett@austintexas.gov
  - Project Manager: Yuejiao Liu, P.E.  
512- 974-7216  
yuejiao.Liu@austintexas.gov
  - Design team: Thu Cao, P.E.  
512-974-7167  
Thu.Cao@austintexas.gov  
Micheal Singleton, P.E.  
512-974-3418  
Micheal.Singleton@austintexas.gov